



CAMERON COUNTY PURCHASING

1100 East Monroe St,
Brownsville, Texas 78520
(956) 544-0871 Fax: (956) 550-7219

ADDENDUM # 5 - PAGE 1 of 2

DATE OUT: 11/14/23

RFP TITLE: DARRELL HESTER JUVENILE DETENTION CENTER SMOKE EVACUATION AND HVAC SYSTEMS UPGRADES

RFP NUMBER # 231001

DEADLINE: November 15, 2023 at 3:00 p.m.

(IN ORDER TO AVOID DISQUALIFICATION – ALL ADDENDUMS MUST BE SIGNED AND RETURNED BY DEADLINE AND INCLUDED IN THE SEALED BID PACKAGE SUBMITTED)

1- Response to request for clarifications during the last job-site visit meeting at Darrell B. Hester Juvenile Detention Center on Thursday, November 2nd, 2023.

Please see response to clarifications from Project Engineering Consultant Ethos Engineering.

Note:

This addendum shall become part of the RFP and all RESPONDERS/PARTICIPANTS shall be bound by its content. All aspects of the scope of work/services not covered herein shall remain the same.

Company Name _____ Phone # _____

Vendor Signature _____ Date _____

Must include and return with RFP package



1126 South Commerce
Harlingen, TX 78550
Off: (956) 230-3435
Fax: (956) 720-0830
www.ethoseng.net

November 13, 2023

Darrell Hester Smoke Evacuation and HVAC Systems Upgrades – RFQ #231001

ADDENDUM NO. 5

A. PURPOSE AND INTENT

This addendum is issued for the purpose of modifying the plans for the project referenced above. This addendum shall become part of the contract and all contractors shall be bound by its content. All aspects of the specifications and drawings not covered herein shall remain the same. The General Conditions and the Special Conditions of the specifications shall govern all parts of the work and apply in full force to this addendum.

B. CLARIFICATIONS

- 1) Section 267210 – Fire Alarm and Smoke Evacuation Systems:
Revised Section 1.3 - B – 2,3 as follows:

B. Smoke evacuation system: Provide the following, including but not limited to:

1. Coordination with fire alarm contractor.
2. Motorized dampers (by mechanical contractor) for smoke evacuation system as shown on drawings and schedules. Dampers shall meet all code requirements (NFPA smoke evacuation system). Coordinate exact requirements of proving end switches (by mechanical contractor) with fire alarm contractor.
3. (Mechanical Contractor to provide) Flow (sail) switches, belt slippage alarms, etc. for smoke evacuation fans and make up air fans. Coordinate exact requirements of with fire alarm contractor.
4. Alarms when actual status does not match commanded status.



11/13/2023